


PIRANHA OFFROAD PRODUCTS P/N BTP150D

'Piranha Off Road products are not associated in any way with Toyota Australia or any of its related companies'

To Suit PRADO 150 SERIES Diesel- late 2009 - 07/2015
 May Not suit some Kakadu Models



PART NUMBER	BTP150D
APPROX FITTING TIME	1 Hour
MAX BATTERY SIZE	300mm L
MAX BATT WEIGHT	23Kg
CYCLE DUTY	Non AGM
TRAY LOCATION	DSF



PARTS INCLUDED WITH TRAY

- 1 X Tray
- 2 X M8 Countersunk
- 3 X M6 Countersunk
- 1 X M6 Hex
- 1 X M6 Wizlock
- 1 X M8 Long
- 1 X M8 Body Washer
- 1 X M8 Wizlock
- 1 X Special Top Mount
- 2 X J Bolt
- 1 X A/C Bracket

RECOMMENDED ISOLATOR

DBE140SF
 or
DBE180-SX

FITTING INSTRUCTIONS

The cradle fits drivers side front

1. Remove bolt from earths on inner guard
2. Remove A/C pipe bracket from inner guard bottom only.
DO NOT LOOSEN TOP NUT (A)
3. Remove bracket from rubber mount on A/C pipe (B)
4. Bolt on new bracket to rubber on A/C pipe
5. Place tray into position and loosely put in all bolts
6. Bolt A/C bracket to tray
7. Tighten all bolts to secure the tray
- 8. Once tray is bolted in, ensure adequate clearance on all A/C pipes, radiator support panel & rear of engine bay**
9. Place battery into position and secure with special top mount

Ensure, before closing the bonnet that all items fitted have adequate clearance